

EXISTING SETBACKS

FRONT YARD = 19'-8"
REAR YARD = 292'-7" (EST.)
NORTH YARD = 5'-5"
SOUTH YARD = 16'-4"

NO PROPOSED CHANGES TO EXISTING BUILDING SETBACKS.

ABBREVIATIONS

E or (E) EXISTING TO REMAIN.
N or (N) NEW TO BE ADDED.
P.A. PLANTED AREA

LEGEND

--- PROPERTY LINE
----- REQUIRED SETBACK LINE

SHEET INDEX:

CO.0 SITE PLAN/PROJECT DATA
C1.0 TOPOGRAPHIC SURVEY
GN-1 2019 CAL GREEN BUILDING CODE MEASURES
GN-2 2019 CAL GREEN BUILDING CODE MEASURES
A1.0 EXISTING FLOOR PLAN & DEMOLITION PLAN
A2.0 PROPOSED FLOOR PLAN
A3.0 ELECTRICAL PLAN, ROOF PLAN & FRONT ELEVATION
A4.0 EXTERIOR ELEVATIONS
A5.0 BUILDING SECTIONS

SCOPE OF WORK:

EXISTING 2-CAR GARAGE TO BE DEMOLISHED AND REBUILT. 285 S.F. ADDITION FOR GARAGE, NEW MASTER BEDROOM TO BE CONSTRUCTED. EXISTING MASTER BATHROOM TO BE REMODELED. EXISTING FRONT DRIVEWAY TO BE RE-LANDSCAPED. NEW 30 S.F. ADDITION.

PROJECT DATA:

SITE ADDRESS: 27361 RAINBOW RIDGE RD
PALOS VERDES PEN CA, 90274

ASSESSORS PARCEL NO.: 7570022007

OCCUPANCY: R1

RESIDENTIAL TYPE: 1-STORY SINGLE FAMILY DWELLING

LEGAL DESCRIPTION: TRACT # 17208; POR. LOT 59

LOT/PARCEL AREA: 34,317 SQFT (PER ASSESSOR)

LOT DIMENSIONS: 93' x 369'

FLOOR AREA: 1,605 S.F. EXISTING
1,939 S.F. PROPOSED

LOT COVERAGE: 2,490 S.F.

BUILDING HEIGHT: 17'-0" (EXISTING, NO CHANGE)

PARKING PROVIDED: (2) SPACES IN GARAGE

OWNERS:

BRIAN AND KERI FOLKS
27361 RAINBOW RIDGE RD.
PALOS VERDES PEN, CA 90274

DESIGNER:

WES HARDING
HARDING DESIGN & CONSTRUCTION
4040 E. VERMONT ST.
LONG BEACH, CA 90814
562.333.6392
INFO@HARDINGCONSTRUCTION.BIZ

APPLICABLE CODES:

THIS PROJECT SHALL COMPLY WITH THE FOLLOWING CODE SECTIONS:

2020 COUNTY OF LOS ANGELES RESIDENTIAL CODE
2020 COUNTY OF LOS ANGELES BUILDING CODE
2020 COUNTY OF LOS ANGELES ELECTRICAL CODE
2020 COUNTY OF LOS ANGELES PLUMBING CODE
2020 COUNTY OF LOS ANGELES MECHANICAL CODE
2020 COUNTY OF LOS ANGELES GREEN BUILDING STANDARDS CODE
2020 COUNTY OF LOS ANGELES EXISTING BUILDING CODE



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENNISULA, CA 90274

OWNERS: BRIAN AND KERI FOLKS

project title/type:

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title:

COVER SHEET

revisions:

R1:

R2:

R3:

R4:

sheet info:

date: 09.29.20

drawn: js

scale: NOTED


reviewed: -

job no: HDC190820

sheet no:


C0.0

Written dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.



2 PROPOSED SITE PLAN
Scale: 1/8" = 1'-0"

VICINITY MAP



AREA CALCULATIONS

LOT AREA	=	34,317 S.F.
(E) SINGLE FAMILY DWELLING	=	1,605 S.F.
(E) COVERED PORCH	=	56 S.F.
(E) 2-CAR GARAGE	=	495 S.F.
(N) ADDITIONS TO SFD	=	334 S.F.
(N) 2-CAR GARAGE	=	443 S.F.
TOTAL HABITABLE SPACE	=	1,939 S.F.
TOTAL NON-HABITABLE SPACE	=	499 S.F.

FOR CITY USE ONLY

NOTE

THIS SURVEY AND MAP ARE THE PROPERTY OF I/WS SURVEYING AND MAY NOT BE MODIFIED, ALTERED, OR CHANGED IN ANY FASHION WITHOUT PRIOR WRITTEN APPROVAL BY I/WS SURVEYING AND THE CLIENT FOR WHOM THE SURVEY WAS PREPARED. THIS PROVISION EXTENDS TO THE RESULTING PLOT OF SAID MAP AND THE COMPUTER DISK OR E-MAIL OF THAT MAP AS PROVIDED TO THE CLIENT. ANY VIOLATION OF THIS PROVISION WILL VOID ANY PROFESSIONAL OBLIGATION OR WARRANTY, EITHER EXPRESSED OR IMPLIED, BY I/WS SURVEYING AS TO SUCH CHANGED MATERIAL.

ALL MEASUREMENTS SHOWN TO PROPERTY LINES (PL) ARE MEASURED AT A PERPENDICULAR (90°) ANGLE TO PROPERTY LINE.

BASIS OF BEARINGS: N 01°39'45" E BEING THE CENTERLINE OF RAINBOW RIDGE ROAD AS PER TRACT MAP NO 17208, MAP BOOK 548 PAGES 29 TO 31 AS FILED IN THE RECORDS OF THE COUNTY OF LOS ANGELES

BENCHMARK: ASSUMED EL=190.13 FEET AT SPK&W STAMPED "LA CO. DPW" AT APPARENT C/L BC

I/WS
SURVEYING

CLIENT:

BRIAN L. FOLKS &
KERI A. FOLKS

PROJECT NO.

18-346B

DATE OF SURVEY:



JULY 2018

ASSESSOR'S I.D. NUMBER:

1510-022-001

LEGAL DESCRIPTION

POR. LOT 59, TRACT NO.
17208 M.B. 548/24-31



MAP ISSUE DATE: 6/5/2019

DATE OF REVISION:

DRAFTED BY: ELB

COMMENTS:

ABBREVIATION LEGEND

N	NORTH
E	EAST
S	SOUTH
W	WEST
AC	ASPHALT CONCRETE
AP	ANGLE POINT
BC	BEGINNING OF CURVE
BM	BENCHMARK
BoS/ToS	BOTTOM/TOP OF STAIR
BS/TS	BOTTOM/TOP OF SLOPE
BW	BACK OF WALK
BX/TX	BOTTOM/TOP OF X
CBW	CONCRETE BLOCK WALL
CL	CENTERLINE
CLF	CHAIN-LINK FENCE
CN	CONCRETE NAIL
C/O	CLEAN OUT
CONC.	CONCRETE
D	DIRT, DIAMETER
DWY	DRIVENWAY
EC	END OF CURVE
EG	EDGE OF GUTTER
EP	EDGE OF PAVEMENT
FF/FS	FINISH FLOOR/SURFACE
FL	FLOW LINE
FD	FOUND
GB	GRADE BREAK
G.M.	GAS METER
G.W.	GUY WIRE
I/L / O/L	INLET/OUTLET
INV.	INVERT
IP	IRON PIPE
L STD.	LIGHT STANDARD
L#1	LEAD AND TACK
LTT	LEAD, TACK, AND TAG
N.A.P.	NOT A PART
NT	NAIL AND TAG
O/S	OFFSET
PC	PROPERTY CORNER
PL	PROPERTY LINE
PLS, LS	LICENSED SURVEYOR
PP	POWER POLE
PROD	PRODUCED
PUE	PUBLIC UTILITY EASEMENT
RBR	REBAR
RHO	RANCHO
RTW	RETAINING WALL
S/W	RIGHT-OF-WAY
RXR	RAILROAD
SDMH	STORM DRAIN MANHOLE
SPK	SPIKE
SPK&W	SPIKE AND WASHER
TC	TOP OF CURB
TEL PL	TELEPHONE POLE
TG	TOP OF GRATE
ToS/BoS	TOP/BOTTOM OF STAIR
W.I.F.	WROUGHT-IRON FENCE
WM	WATER METER
W.H.	WELL HOLE

SYMBOL LEGEND

- ELECTRIC METER
- PILLAR (DRAWN TO SCALE)
-

LINE TYPE LEGEND

PROPERTY LINE	---
CENTERLINE	—C—C—
EXISTING FENCE	—X—X—
EXISTING WALL	—X—X—

BOUNDARY/TOPOGRAPHIC SURVEY

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA 90274

LICENSED SURVEYOR:

ALL MAPS, PLATS, REPORTS, DESCRIPTIONS, OR OTHER DOCUMENTS ARE PREPARED UNDER THE RESPONSIBLE CHARGE OF A CALIFORNIA PROFESSIONAL LAND SURVEYOR, LICENSED TO PRACTICE LAND SURVEYING IN THE STATE OF CALIFORNIA. CHRISTOPHER N. VASSALLO, P.L.S. 8418, PURSUANT TO THE PROFESSIONAL LAND SURVEYOR'S ACT, BUSINESS AND PROFESSIONS CODE, CHAPTER 15, SECTIONS 8100-8805.

SHEET:

C1.0

PREPARED BY:
I/WS SURVEYING
2556 VIA TEJON
PALOS VERDES ESTATES
CALIFORNIA 90274-1348
PHONE: 310.791.0904
FAX: 310.791.0914

2019 CALIFORNIA GREEN BUILDING STANDARDS CODE

RESIDENTIAL MANDATORY MEASURES, SHEET 1 (January 2020, Includes August 2019 Supplement)



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274
OWNERS: BRIAN AND KERI FOLKS

Y N/A RESPON. PARTY = YES = NOT APPLICABLE = RESPONSIBLE PARTY (i.e. ARCHITECT, ENGINEER, OWNER, CONTRACTOR, INSPECTOR ETC.)

CHAPTER 3 GREEN BUILDING SECTION 301 GENERAL

301.1 SCOPE. Buildings shall be designed to include the green building measures specified as mandatory in the application checklists contained in this code. Voluntary green building measures are also included in the application checklists and may be included in the design and construction of structures covered by this code, but are not required unless adopted by a city, county, or city and county as specified in Section 101.7.

301.1.1 Additions and alterations. [HCD] The mandatory provisions of Chapter 4 shall be applied to additions or alterations of existing residential buildings where the addition or alteration increases the building's conditioned area, volume, or size. The requirements shall apply only to and/or within the specific area of the addition or alteration.

Note: On and after January 1, 2014, residential buildings undergoing permitted alterations, additions, or improvements shall replace noncompliant plumbing fixtures with water-conserving plumbing fixtures. Plumbing fixture replacement is required prior to issuance of a certificate of final completion, certificate of occupancy or final permit approval by the local building department. See Civil Code Section 1101.1, et seq., for the definition of a noncompliant plumbing fixture, types of residential buildings affected and other important enactment dates.

301.2 LOW-RISE AND HIGH-RISE RESIDENTIAL BUILDINGS. [HCD] The provisions of individual sections of CALGreen may apply to either low-rise residential buildings high-rise residential buildings, or both. Individual sections will be designated by banners to indicate where the section applies specifically to low-rise only (LR) or high-rise only (HR). When the section applies to both low-rise and high-rise buildings, no banner will be used.

SECTION 302 MIXED OCCUPANCY BUILDINGS

302.1 MIXED OCCUPANCY BUILDINGS. In mixed occupancy buildings, each portion of a building shall comply with the specific green building measures applicable to each specific occupancy.

ABBREVIATION DEFINITIONS:

HCD Department of Housing and Community Development
BSC California Building Standards Commission
DSA-SS Division of the State Architect, Structural Safety
OSHDP Office of Statewide Health Planning and Development
LR Low Rise
HR High Rise
AA Additions and Alterations
N New

CHAPTER 4 RESIDENTIAL MANDATORY MEASURES

DIVISION 4.1 PLANNING AND DESIGN

SECTION 4.102 DEFINITIONS

4.102.1 DEFINITIONS
The following terms are defined in Chapter 2 (and are included here for reference)

FRENCH DRAIN. A trench, hole or other depressed area loosely filled with rock, gravel, fragments of brick or similar pervious material used to collect or channel drainage or runoff water.

WATTLES. Wattles are used to reduce sediment in runoff. Wattles are often constructed of natural plant materials such as hay, straw or similar material shaped in the form of tubes and placed on a downflow slope. Wattles are also used for perimeter and inlet controls.

4.106 SITE DEVELOPMENT

4.106.1 GENERAL. Preservation and use of available natural resources shall be accomplished through evaluation and careful planning to minimize negative effects on the site and adjacent areas. Preservation of slopes, management of storm water drainage and erosion controls shall comply with this section.

4.106.2 STORM WATER DRAINAGE AND RETENTION DURING CONSTRUCTION. Projects which disturb less than one acre of soil and are not part of a larger common plan of development which in total disturbs one acre or more, shall manage storm water drainage during construction. In order to manage storm water drainage during construction, one or more of the following measures shall be implemented to prevent flooding of adjacent property, prevent erosion and retain soil runoff on the site.

- Retention basins of sufficient size shall be utilized to retain storm water on the site.
- Where storm water is conveyed to a public drainage system, collection point, gutter or similar disposal method, water shall be filtered by use of a barrier system, wattle or other method approved by the enforcing agency.
- Compliance with a lawfully enacted storm water management ordinance.

Note: Refer to the State Water Resources Control Board for projects which disturb one acre or more of soil, or are part of a larger common plan of development which in total disturbs one acre or more of soil.

(Website: https://www.waterboards.ca.gov/water_issues/programs/stormwater/construction.html)

4.106.3 GRADING AND PAVING. Construction plans shall indicate how the site grading or drainage system will manage all surface water flows to keep water from entering buildings. Examples of methods to manage surface water include, but are not limited to, the following:

- Swales
- Water collection and disposal systems
- French drains
- Water retention gardens
- Other water measures which keep surface water away from buildings and aid in groundwater recharge.

Exception: Additions and alterations not altering the drainage path.

4.106.4 Electric vehicle (EV) charging for new construction. New construction shall comply with Sections 4.106.4.1, 4.106.4.2, or 4.106.4.3 to facilitate future installation and use of EV chargers. Electric vehicle supply equipment (EVSE) shall be installed in accordance with the *California Electrical Code*, Article 625.

Exceptions:

- On a case-by-case basis, where the local enforcing agency has determined EV charging and infrastructure are not feasible based upon one or more of the following conditions:
 - Where there is no commercial power supply.
 - Where there is evidence substantiating that meeting the requirements will alter the local utility infrastructure design requirements on the utility side of the meter so as to increase the utility side cost to the homeowner or the developer by more than \$400.00 per dwelling unit.
- Accessory Dwelling Units (ADU) and Junior Accessory Dwelling Units (JADU) without additional parking facilities.

4.106.4.1 New one- and two-family dwellings and townhouses with attached private garages. For each dwelling unit, install a listed raceway to accommodate a dedicated 208/240-volt branch circuit. The raceway shall not be less than trade size 1 (nominal 1-inch inside diameter). The raceway shall originate at the main service or subpanel and shall terminate into a listed cabinet, box or other enclosure in close proximity to the proposed location of an EV charger. Raceways are required to be continuous at enclosed, inaccessible or concealed areas and spaces. The service panel and/or subpanel shall provide capacity to install a 40-ampere minimum dedicated branch circuit and space(s) reserved to permit installation of a branch circuit overcurrent protective device.

4.106.4.1.1 Identification. The service panel or subpanel circuit directory shall identify the overcurrent protective device space(s) reserved for future EV charging as "EV CAPABLE". The raceway termination location shall be permanently and visibly marked as "EV CAPABLE".

4.106.4.2 New multifamily dwellings. If residential parking is available, ten (10) percent of the total number of parking spaces on a building site, provided for all types of parking facilities, shall be electric vehicle charging spaces (EV spaces) capable of supporting future EVSE. Calculations for the required number of EV spaces shall be rounded up to the nearest whole number.

Notes:

- Construction documents are intended to demonstrate the project's capability and capacity for facilitating future EV charging.
- There is no requirement for EV spaces to be constructed or available until EV chargers are installed for use.

4.106.4.2.1 Electric vehicle charging space (EV space) locations. Construction documents shall indicate the location of proposed EV spaces. Where common use parking is provided at least one EV space shall be located in the common use parking area and shall be available for use by all residents.

4.106.4.2.1.1 Electric Vehicle Charging Stations (EVCS) When EV chargers are installed, EV spaces required by Section 4.106.2.2, Item 3, shall comply with at least one of the following options:

- The EV space shall be located adjacent to an accessible parking space meeting the requirements of the *California Building Code*, Chapter 11A, to allow use of the EV charger from the accessible parking space.
- The EV space shall be located on an accessible route, as defined in the *California Building Code*, Chapter 2, to the building.

Exception: Electric vehicle charging stations designed and constructed in compliance with the *California Building Code*, Chapter 11B, are not required to comply with Section 4.106.4.2.1.1 and Section 4.106.4.2.2, Item 3.

Note: Electric Vehicle charging stations serving public housing are required to comply with the *California Building Code*, Chapter 11B.

4.106.4.2.2 Electric vehicle charging space (EV space) dimensions. The EV space shall be designed to comply with the following:

- The minimum length of each EV space shall be 18 feet (5486 mm).
 - The minimum width of each EV space shall be 9 feet (2743 mm).
 - One in every 25 EV spaces, but not less than one EV space, shall have an 8-foot (2438 mm) wide minimum aisle. A 5-foot (1524 mm) wide minimum aisle shall be permitted provided the minimum width of the EV space is 12 feet (3658 mm).
- a. Surface slope for this EV space and the aisle shall not exceed 1 unit vertical in 48 units horizontal (2.083 percent slope) in any direction.

4.106.4.2.3 Single EV space required. Install a listed raceway capable of accommodating a 208/240-volt dedicated branch circuit. The raceway shall not be less than trade size 1 (nominal 1-inch inside diameter). The raceway shall originate at the main service or subpanel and shall terminate into a listed cabinet, box or enclosure in close proximity to the proposed location of the EV space. Construction documents shall identify the raceway termination point. The service panel and/or subpanel shall provide capacity to install a 40-ampere minimum dedicated branch circuit and space(s) reserved to permit installation of a branch circuit overcurrent protective device.

4.106.4.2.4 Multiple EV spaces required. Construction documents shall indicate the raceway termination point and proposed location of future EV spaces and EV chargers. Construction documents shall also provide information on amperage of future EVSE, raceway method(s), wiring schematics and electrical load calculations to verify that the electrical panel service capacity and electrical system, including any on-site distribution transformer(s), have sufficient capacity to simultaneously charge all EVs at all required EV spaces at the full rated amperage of the EVSE. Plan design shall be based upon a 40-ampere minimum branch circuit. Required raceways and related components that are planned to be installed underground, enclosed, inaccessible or in concealed areas and spaces shall be installed at the time of original construction.

4.106.4.2.5 Identification. The service panel or subpanel circuit directory shall identify the overcurrent protective device space(s) reserved for future EV charging purposes as "EV CAPABLE" in accordance with the *California Electrical Code*.

4.106.4.3 New hotels and motels. All newly constructed hotels and motels shall provide EV spaces capable of supporting future installation of EVSE. The construction documents shall identify the location of the EV spaces.

Notes:

- Construction documents are intended to demonstrate the project's capability and capacity or facilitating future EV charging.
- There is no requirement for EV spaces to be constructed or available until EV chargers are installed for use.

4.106.4.3.1 Number of required EV spaces. The number of required EV spaces shall be based on the total number of parking spaces provided for all types of parking facilities in accordance with Table 4.106.4.3.1. Calculations for the required number of EV spaces shall be rounded up to the nearest whole number.

TABLE 4.106.4.3.1	
TOTAL NUMBER OF PARKING SPACES	NUMBER OF REQUIRED EV SPACES
0-9	0
10-25	1
26-50	2
51-75	4
76-100	5
101-150	7
151-200	10
201 and over	6 percent of total

4.106.4.3.2 Electric vehicle charging space (EV space) dimensions. The EV spaces shall be designed to comply with the following:

- The minimum length of each EV space shall be 18 feet (5486mm).
- The minimum width of each EV space shall be 9 feet (2743mm)

4.106.4.3.3 Single EV space required. When a single EV space is required, the EV space shall be designed in accordance with Section 4.106.4.2.3.

4.106.4.3.4 Multiple EV spaces required. When multiple EV spaces are required, the EV spaces shall be designed in accordance with Section 4.106.4.2.4.

4.106.4.3.5 Identification. The service panels or sub-panels shall be identified in accordance with Section 4.106.4.2.5.

4.106.4.3.6 Accessible EV spaces. In addition to the requirements in Section 4.106.4.3, EV spaces for hotels/motels and all EVSE, when installed, shall comply with the accessibility provisions for the EV charging stations in the *California Building Code*, Chapter 11B.

DIVISION 4.2 ENERGY EFFICIENCY

4.201 GENERAL

4.201.1 SCOPE. For the purposes of mandatory energy efficiency standards in this code, the California Energy Commission will continue to adopt mandatory standards.

DIVISION 4.3 WATER EFFICIENCY AND CONSERVATION

4.303 INDOOR WATER USE

4.303.1 WATER CONSERVING PLUMBING FIXTURES AND FITTINGS. Plumbing fixtures (water closets and urinals) and fittings (faucets and showerheads) shall comply with the sections 4.303.1.1, 4.303.1.2, 4.303.1.3, and 4.303.4.4.

Note: All noncompliant plumbing fixtures in any residential real property shall be replaced with water-conserving plumbing fixtures. Plumbing fixture replacement is required prior to issuance of a certificate of final completion, certificate of occupancy, or final permit approval by the local building department. See Civil Code Section 1101.1, et seq., for the definition of a noncompliant plumbing fixture, types of residential buildings affected and other important enactment dates.

4.303.1.1 Water Closets. The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-type Toilets.

Note: The effective flush volume of dual flush toilets is defined as the composite, average flush volume of two reduced flushes and one full flush.

4.303.1.2 Urinals. The effective flush volume of wall mounted urinals shall not exceed 0.125 gallons per flush. The effective flush volume of all other urinals shall not exceed 0.5 gallons per flush.

4.303.1.3 Showerheads.

4.303.1.3.1 Single Showerhead. Showerheads shall have a maximum flow rate of not more than 1.8 gallons per minute at 80 psi. Showerheads shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Showerheads.

4.303.1.3.2 Multiple showerheads serving one shower. When a shower is served by more than one showerhead, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 1.8 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.

Note: A hand-held shower shall be considered a showerhead.

4.303.1.4 Faucets.

4.303.1.4.1 Residential Lavatory Faucets. The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not be less than 0.8 gallons per minute at 20 psi.

4.303.1.4.2 Lavatory Faucets in Common and Public Use Areas. The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.

4.303.1.4.3 Metering Faucets. Metering faucets when installed in residential buildings shall not deliver more than 0.2 gallons per cycle.

4.303.1.4.4 Kitchen Faucets. The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.

Note: Where complying faucets are unavailable, aerators or other means may be used to achieve reduction.

4.303.2 STANDARDS FOR PLUMBING FIXTURES AND FITTINGS. Plumbing fixtures and fittings shall be installed in accordance with the *California Plumbing Code*, and shall meet the applicable standards referenced in Table 1701.1 of the *California Plumbing Code*.

NOTE:
THIS TABLE COMPILES THE DATA IN SECTION 4.303.1, AND IS INCLUDED AS A CONVENIENCE FOR THE USER.

TABLE - MAXIMUM FIXTURE WATER USE	
FIXTURE TYPE	FLOW RATE
SHOWER HEADS (RESIDENTIAL)	1.8 GMP @ 80 PSI
LAVATORY FAUCETS (RESIDENTIAL)	MAX. 1.2 GPM @ 60 PSI MIN. 0.8 GPM @ 20 PSI
LAVATORY FAUCETS IN COMMON & PUBLIC USE AREAS	0.5 GPM @ 60 PSI
KITCHEN FAUCETS	1.8 GPM @ 60 PSI
METERING FAUCETS	0.2 GAL/CYCLE
WATER CLOSET	1.28 GAL/FLUSH
URINALS	0.125 GAL/FLUSH

4.304 OUTDOOR WATER USE

4.304.1 OUTDOOR POTABLE WATER USE IN LANDSCAPE AREAS. Residential developments shall comply with a local water efficient landscape ordinance or the current California Department of Water Resources' Model Water Efficient Landscape Ordinance (MWELO), whichever is more stringent.

NOTES:

- The Model Water Efficient Landscape Ordinance (MWELO) is located in the *California Code Regulations*, Title 23, Chapter 2.7, Division 2. MWELO and supporting documents, including water budget calculator, are available at: <https://www.water.ca.gov/>

DIVISION 4.4 MATERIAL CONSERVATION AND RESOURCE EFFICIENCY

4.406 ENHANCED DURABILITY AND REDUCED MAINTENANCE

4.406.1 RODENT PROOFING. Annular spaces around pipes, electric cables, conduits or other openings in sole/bottom plates at exterior walls shall be protected against the passage of rodents by closing such openings with cement mortar, concrete masonry or a similar method acceptable to the enforcing agency.

4.408 CONSTRUCTION WASTE REDUCTION, DISPOSAL AND RECYCLING

4.408.1 CONSTRUCTION WASTE MANAGEMENT. Recycle and/or salvage for reuse a minimum of 65 percent of the non-hazardous construction and demolition waste in accordance with either Section 4.408.2, 4.408.3 or 4.408.4, or meet a more stringent local construction and demolition waste management ordinance.

Exceptions:

- Excavated soil and land-clearing debris.
- Alternate waste reduction methods developed by working with local agencies if diversion or recycle facilities capable of compliance with this item do not exist or are not located reasonably close to the jobsite.
- The enforcing agency may make exceptions to the requirements of this section when isolated jobsites are located in areas beyond the haul boundaries of the diversion facility.

4.408.2 CONSTRUCTION WASTE MANAGEMENT PLAN. Submit a construction waste management plan in conformance with Items 1 through 5. The construction waste management plan shall be updated as necessary and shall be available during construction for examination by the enforcing agency.

- Identify the construction and demolition waste materials to be diverted from disposal by recycling, reuse on the project or salvage for future use or sale.
- Specify if construction and demolition waste materials will be sorted on-site (source separated) or bulk mixed (single stream).
- Identify diversion facilities where the construction and demolition waste material collected will be taken.
- Identify construction methods employed to reduce the amount of construction and demolition waste generated.
- Specify that the amount of construction and demolition waste materials diverted shall be calculated by weight or volume, but not by both.

4.408.3 WASTE MANAGEMENT COMPANY. Utilize a waste management company, approved by the enforcing agency, which can provide verifiable documentation that the percentage of construction and demolition waste material diverted from the landfill complies with Section 4.408.1.

Note: The owner or contractor may make the determination if the construction and demolition waste materials will be diverted by a waste management company.

4.408.4 WASTE STREAM REDUCTION ALTERNATIVE [LR]. Projects that generate a total combined weight of construction and demolition waste disposed of in landfills, which do not exceed 3.4 lbs./sq. ft. of the building area shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1

4.408.4.1 WASTE STREAM REDUCTION ALTERNATIVE. Projects that generate a total combined weight of construction and demolition waste disposed of in landfills, which do not exceed 2 pounds per square foot of the building area, shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1

4.408.5 DOCUMENTATION. Documentation shall be provided to the enforcing agency which demonstrates compliance with Section 4.408.2, Items 1 through 5, Section 4.408.3 or Section 4.408.4..

Notes:

- Sample forms found in "A Guide to the California Green Building Standards Code (Residential)" located at www.hcd.ca.gov/CALGreen.html may be used to assist in documenting compliance with this section.
- Mixed construction and demolition debris (C & D) processors can be located at the California Department of Resources Recycling and Recovery (CalRecycle).

4.410 BUILDING MAINTENANCE AND OPERATION

4.410.1 OPERATION AND MAINTENANCE MANUAL. At the time of final inspection, a manual, compact disc, web-based reference or other media acceptable to the enforcing agency which includes all of the following shall be placed in the building:

- Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.
- Operation and maintenance instructions for the following:
 - Equipment and appliances, including water-saving devices and systems, HVAC systems, photovoltaic systems, electric vehicle chargers, water-heating systems and other major appliances and equipment.
 - Roof and yard drainage, including gutters and downspouts.
 - Space conditioning systems, including condensers and air filters.
 - Landscape irrigation systems.
 - Water reuse systems.
- Information from local utility, water and waste recovery providers on methods to further reduce resource consumption, including recycle programs and locations.
- Public transportation and/or carpool options available in the area.
- Educational material on the positive impacts of an interior relative humidity between 30-60 percent and what methods an occupant may use to maintain the relative humidity level in that range.
- Information about water-conserving landscape and irrigation design and controllers which conserve water.
- Instructions for maintaining gutters and downspouts and the importance of diverting water at least 5 feet away from the foundation.
- Information on required routine maintenance measures, including, but not limited to, caulking, painting, grading around the building, etc.
- Information about state solar energy and incentive programs available.
- A copy of all special inspections verifications required by the enforcing agency or this code.

4.410.2 RECYCLING BY OCCUPANTS. Where 5 or more multifamily dwelling units are constructed on a building site, provide readily accessible area(s) that serves all buildings on the site and are identified for the depositing, storage and collection of non-hazardous materials for recycling, including (at a minimum) paper, corrugated cardboard, glass, plastics, organic waste, and metals, or meet a lawfully enacted local recycling ordinance, if more restrictive.

Exception: Rural jurisdictions that meet and apply for the exemption in Public Resources Code Section 42649.82 (a)(2)(A) et seq. are not required to comply with the organic waste portion of this section.

DIVISION 4.5 ENVIRONMENTAL QUALITY

SECTION 4.501 GENERAL

4.501.1 Scope

The provisions of this chapter shall outline means of reducing the quality of air contaminants that are odorous, irritating and/or harmful to the comfort and well being of a building's installers, occupants and neighbors.

SECTION 4.502 DEFINITIONS

5.102.1 DEFINITIONS

The following terms are defined in Chapter 2 (and are included here for reference)

AGRIFIBER PRODUCTS. Agrifiber products include wheatboard, strawboard, panel substrates and door cores, not including furniture, fixtures and equipment (FF&E) not considered base building elements.

COMPOSITE WOOD PRODUCTS. Composite wood products include hardwood plywood, particleboard and medium density fiberboard. "Composite wood products" does not include hardboard, structural plywood, structural panels, structural composite lumber, oriented strand board, glued laminated timber, prefabricated wood I-joists or finger-jointed lumber, all as specified in California Code of regulations (CCR), title 17, Section 93120.1.

DIRECT-VENT APPLIANCE. A fuel-burning appliance with a sealed combustion system that draws all air for combustion from the outside atmosphere and discharges all flue gases to the outside atmosphere.

project title/type:

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title:

CAL GREEN NOTES

revisions:

R1:

R2:

R3:

R4:

sheet info:

date: 09.29.20

drawn: js

scale: NOTED

reviewed: -

job no: HDC190820

sheet no:

GN-1

When dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to the office for approval before proceeding with fabrications.

2019 CALIFORNIA GREEN BUILDING STANDARDS CODE
RESIDENTIAL MANDATORY MEASURES, SHEET 1 (January 2020, Includes August 2019 Supplement)

Y N/A RESPON. PARTY
= YES NOT APPLICABLE RESPONSIBLE PARTY (i.e. ARCHITECT, ENGINEER, OWNER, CONTRACTOR, INSPECTOR, ETC.)



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274
OWNERS: BRIAN AND KERI FOLKS

CHAPTER 7
INSTALLER & SPECIAL INSPECTOR QUALIFICATIONS

702 QUALIFICATIONS

702.1 INSTALLER TRAINING. HVAC system installers shall be trained and certified in the proper installation of HVAC systems including ducts and equipment by a nationally or regionally recognized training or certification program. Uncertified persons may perform HVAC installations when under the direct supervision and responsibility of a person trained and certified to install HVAC systems or contractor licensed to install HVAC systems. Examples of acceptable HVAC training and certification programs include but are not limited to the following:

1. State certified apprenticeship programs.
2. Public utility training programs.
3. Training programs sponsored by trade, labor or statewide energy consulting or verification organizations.
4. Programs sponsored by manufacturing organizations.
5. Other programs acceptable to the enforcing agency.

702.2 SPECIAL INSPECTION [HCD]. When required by the enforcing agency, the owner or the responsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition to other certifications or qualifications acceptable to the enforcing agency, the following certifications or education may be considered by the enforcing agency when evaluating the qualifications of a special inspector:

1. Certification by a national or regional green building program or standard publisher.
2. Certification by a statewide energy consulting or verification organization, such as HERS raters, building performance contractors, and home energy auditors.
3. Successful completion of a third party apprentice training program in the appropriate trade.
4. Other programs acceptable to the enforcing agency.

- Notes:**
1. Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code.
 2. HERS raters are special inspectors certified by the California Energy Commission (CEC) to rate homes in California according to the Home Energy Rating System (HERS).

[BSC] When required by the enforcing agency, the owner or the responsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition, the special inspector shall have a certification from a recognized state, national or international association, as determined by the local agency. The area of certification shall be closely related to the primary job function, as determined by the local agency.

Note: Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code.

703 VERIFICATIONS

703.1 DOCUMENTATION. Documentation used to show compliance with this code shall include but is not limited to, construction documents, plans, specifications, builder or installer certification, inspection reports, or other methods acceptable to the enforcing agency which demonstrate substantial conformance. When specific documentation or special inspection is necessary to verify compliance, that method of compliance will be specified in the appropriate section or identified applicable checklist.

project title/type:

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title:

CAL GREEN NOTES

revisions:

R1:

R2:

R3:

R4:

sheet info:

date: 09.29.20

drawn: js

scale: NOTED

reviewed: -

job no: HDC190820

sheet no:

GN-2

When dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to the office for approval before proceeding with fabrications.

MAXIMUM INCREMENTAL REACTIVITY (MIR). The maximum change in weight of ozone formed by adding a compound to the "Base Reactive Organic Gas (ROG) Mixture" per weight of compound added, expressed to hundredths of a gram (g O₃/g ROG).
Note: MIR values for individual compounds and hydrocarbon solvents are specified in CCR, Title 17, Sections 94700 and 94701.

MOISTURE CONTENT. The weight of the water in wood expressed in percentage of the weight of the oven-dry wood.

PRODUCT-WEIGHTED MIR (PWMIR). The sum of all weighted-MIR for all ingredients in a product subject to this article. The PWMIR is the total product reactivity expressed to hundredths of a gram of ozone formed per gram of product (excluding container and packaging).
Note: PWMIR is calculated according to equations found in CCR, Title 17, Section 94521 (a).

REACTIVE ORGANIC COMPOUND (ROC). Any compound that has the potential, once emitted, to contribute to ozone formation in the troposphere.

VOC. A volatile organic compound (VOC) broadly defined as a chemical compound based on carbon chains or rings with vapor pressures greater than 0.1 millimeters of mercury at room temperature. These compounds typically contain hydrogen and may contain oxygen, nitrogen and other elements. See CCR Title 17, Section 94508(a).

4.503 FIREPLACES

4.503.1 GENERAL. Any installed gas fireplace shall be a direct-vent sealed-combustion type. Any installed woodstove or pellet stove shall comply with U.S. EPA New Source Performance Standards (NSPS) emission limits as applicable, and shall have a permanent label indicating they are certified to meet the emission limits. Woodstoves, pellet stoves and fireplaces shall also comply with applicable local ordinances.

4.504 POLLUTANT CONTROL

4.504.1 COVERING OF DUCT OPENINGS & PROTECTION OF MECHANICAL EQUIPMENT DURING CONSTRUCTION. At the time of rough installation, during storage on the construction site and until final startup of the heating, cooling and ventilating equipment, all duct and other related air distribution component openings shall be covered with tape, plastic, sheet metal or other methods acceptable to the enforcing agency to reduce the amount of water, dust or debris which may enter the system.

4.504.2 FINISH MATERIAL POLLUTANT CONTROL. Finish materials shall comply with this section.

4.504.2.1 Adhesives, Sealants and Caulks. Adhesives, sealant and caulks used on the project shall meet the requirements of the following standards unless more stringent local or regional air pollution or air quality management district rules apply:

1. Adhesives, adhesive bonding primers, adhesive primers, sealants, sealant primers and caulks shall comply with local or regional air pollution control or air quality management district rules where applicable or SCAQMD Rule 1168 VOC limits, as shown in Table 4.504.1 or 4.504.2, as applicable. Such products also shall comply with the Rule 1168 prohibition on the use of certain toxic compounds (chloroform, ethylene dichloride, methylene chloride, perchloroethylene and trichloroethylene), except for aerosol products, as specified in Subsection 2 below.
2. Aerosol adhesives, and smaller unit sizes of adhesives, and sealant or caulking compounds (in units of product, less packaging, which do not weigh more than 1 pound and do not consist of more than 16 fluid ounces) shall comply with statewide VOC standards and other requirements, including prohibitions on use of certain toxic compounds, of *California Code of Regulations*, Title 17, commencing with section 94507.

4.504.2.2 Paints and Coatings. Architectural paints and coatings shall comply with VOC limits in Table 1 of the ARB Architectural Suggested Control Measure, as shown in Table 4.504.3, unless more stringent local limits apply. The VOC content limit for coatings that do not meet the definitions for the specialty coatings categories listed in Table 4.504.3 shall be determined by classifying the coating as a Flat, Nonflat or Nonflat-High Gloss coating, based on its gloss, as defined in subsections 4.21, 4.36, and 4.37 of the 2007 California Air Resources Board, Suggested Control Measure, and the corresponding Flat, Nonflat or Nonflat-High Gloss VOC limit in Table 4.504.3 shall apply.

4.504.2.3 Aerosol Paints and Coatings. Aerosol paints and coatings shall meet the Product-weighted MIR Limits for ROC in Section 94522(a)(2) and other requirements, including prohibitions on use of certain toxic compounds and ozone depleting substances, in Sections 94522(e)(1) and (f)(1) of *California Code of Regulations*, Title 17, commencing with Section 94520; and in areas under the jurisdiction of the Bay Area Air Quality Management District additionally comply with the percent VOC by weight of product limits of Regulation 8, Rule 49.

4.504.2.4 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:

1. Manufacturer's product specification.
2. Field verification of on-site product containers.

TABLE 4.504.1 - ADHESIVE VOC LIMIT ^{1,2}	
(Less Water and Less Exempt Compounds in Grams per Liter)	
ARCHITECTURAL APPLICATIONS	VOC LIMIT
INDOOR CARPET ADHESIVES	50
CARPET PAD ADHESIVES	50
OUTDOOR CARPET ADHESIVES	150
WOOD FLOORING ADHESIVES	100
RUBBER FLOOR ADHESIVES	60
SUBFLOOR ADHESIVES	50
CERAMIC TILE ADHESIVES	65
VCT & ASPHALT TILE ADHESIVES	50
DRYWALL & PANEL ADHESIVES	50
COVE BASE ADHESIVES	50
MULTIPURPOSE CONSTRUCTION ADHESIVE	70
STRUCTURAL GLAZING ADHESIVES	100
SINGLE-PLY ROOF MEMBRANE ADHESIVES	250
OTHER ADHESIVES NOT LISTED	50
SPECIALTY APPLICATIONS	
PVC WELDING	510
CPVC WELDING	490
ABS WELDING	325
PLASTIC CEMENT WELDING	250
ADHESIVE PRIMER FOR PLASTIC	550
CONTACT ADHESIVE	80
SPECIAL PURPOSE CONTACT ADHESIVE	250
STRUCTURAL WOOD MEMBER ADHESIVE	140
TOP & TRIM ADHESIVE	250
SUBSTRATE SPECIFIC APPLICATIONS	
METAL TO METAL	30
PLASTIC FOAMS	50
POROUS MATERIAL (EXCEPT WOOD)	50
WOOD	30
FIBERGLASS	80

1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL BE ALLOWED.

2. FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THIS TABLE, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168.

TABLE 4.504.2 - SEALANT VOC LIMIT	
(Less Water and Less Exempt Compounds in Grams per Liter)	
SEALANTS	VOC LIMIT
ARCHITECTURAL	250
MARINE DECK	760
NONMEMBRANE ROOF	300
ROADWAY	250
SINGLE-PLY ROOF MEMBRANE	450
OTHER	420
SEALANT PRIMERS	
ARCHITECTURAL	
NON-POROUS	250
POROUS	775
MODIFIED BITUMINOUS	500
MARINE DECK	760
OTHER	750

TABLE 4.504.3 - VOC CONTENT LIMITS FOR ARCHITECTURAL COATINGS ^{2,3}	
GRAMS OF VOC PER LITER OF COATING, LESS WATER & LESS EXEMPT COMPOUNDS	
COATING CATEGORY	VOC LIMIT
FLAT COATINGS	50
NON-FLAT COATINGS	100
NONFLAT-HIGH GLOSS COATINGS	150
SPECIALTY COATINGS	
ALUMINUM ROOF COATINGS	400
BASEMENT SPECIALTY COATINGS	400
BITUMINOUS ROOF COATINGS	50
BITUMINOUS ROOF PRIMERS	350
BOND BREAKERS	350
CONCRETE CURING COMPOUNDS	350
CONCRETE/MASONRY SEALERS	100
DRIVEWAY SEALERS	50
DRY FOG COATINGS	150
FAUX FINISHING COATINGS	350
FIRE RESISTIVE COATINGS	350
FLOOR COATINGS	100
FORM-RELEASE COMPOUNDS	250
GRAPHIC ARTS COATINGS (SIGN PAINTS)	500
HIGH TEMPERATURE COATINGS	420
INDUSTRIAL MAINTENANCE COATINGS	250
LOW SOLIDS COATINGS ¹	120
MAGNESITE CEMENT COATINGS	450
MASTIC TEXTURE COATINGS	100
METALLIC PIGMENTED COATINGS	500
MULTICOLOR COATINGS	250
PRETREATMENT WASH PRIMERS	420
PRIMERS, SEALERS, & UNDERCOATERS	100
REACTIVE PENETRATING SEALERS	350
RECYCLED COATINGS	250
ROOF COATINGS	50
RUST PREVENTATIVE COATINGS	250
SHELLACS	
CLEAR	730
OPAQUE	550
SPECIALTY PRIMERS, SEALERS & UNDERCOATERS	100
STAINS	250
STONE CONSOLIDANTS	450
SWIMMING POOL COATINGS	340
TRAFFIC MARKING COATINGS	100
TUB & TILE REFINISH COATINGS	420
WATERPROOFING MEMBRANES	250
WOOD COATINGS	275
WOOD PRESERVATIVES	350
ZINC-RICH PRIMERS	340

1. GRAMS OF VOC PER LITER OF COATING, INCLUDING WATER & EXEMPT COMPOUNDS
2. THE SPECIFIED LIMITS REMAIN IN EFFECT UNLESS REVISED LIMITS ARE LISTED IN SUBSEQUENT COLUMNS IN THE TABLE.
3. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, FEB. 1, 2008. MORE INFORMATION IS AVAILABLE FROM THE AIR RESOURCES BOARD.

TABLE 4.504.5 - FORMALDEHYDE LIMITS ¹	
MAXIMUM FORMALDEHYDE EMISSIONS IN PARTS PER MILLION	
PRODUCT	CURRENT LIMIT
HARDWOOD PLYWOOD VENEER CORE	0.05
HARDWOOD PLYWOOD COMPOSITE CORE	0.05
PARTICLE BOARD	0.09
MEDIUM DENSITY FIBERBOARD	0.11
THIN MEDIUM DENSITY FIBERBOARD ²	0.13

1. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIF. AIR RESOURCES BOARD, AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD AS TESTED IN ACCORDANCE WITH ASTM E 1333. FOR ADDITIONAL INFORMATION, SEE CALIF. CODE OF REGULATIONS, TITLE 17, SECTIONS 93120 THROUGH 93120.12.

2. THIN MEDIUM DENSITY FIBERBOARD HAS A MAXIMUM THICKNESS OF 5/16" (8 MM).

DIVISION 4.5 ENVIRONMENTAL QUALITY (continued)

4.504.3 CARPET SYSTEMS. All carpet installed in the building interior shall meet the testing and product requirements of at least one of the following:

1. Carpet and Rug Institute's Green Label Plus program.
2. California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers" Version 1.1, February 2010 (also known as Specification 01350).
3. NSF/ANSI 140 at the Gold level.
4. Scientific Certifications Systems Indoor Advantage[®] Gold.

4.504.3.1 Carpet cushion. All carpet cushion installed in the building interior shall meet the requirements of the Carpet and Rug Institute's Green Label program.

4.504.3.2 Carpet adhesive. All carpet adhesive shall meet the requirements of Table 4.504.1.

4.504.4 RESILIENT FLOORING SYSTEMS. Where resilient flooring is installed, at least 80% of floor area receiving resilient flooring shall comply with one or more of the following:

1. Products compliant with the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," Version 1.1, February 2010 (also known as Specification 01350), certified as a CHPS Low-Emitting Material in the Collaborative for High Performance Schools (CHPS) High Performance Products Database.
2. Products certified under UL GREENGUARD Gold (formerly the Greenguard Children & Schools program).
3. Certification under the Resilient Floor Covering Institute (RFCI) FloorScore program.
4. Meet the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers", Version 1.1, February 2010 (also known as Specification 01350).

4.504.5 COMPOSITE WOOD PRODUCTS. Hardwood plywood, particleboard and medium density fiberboard composite wood products used on the interior or exterior of the buildings shall meet the requirements for formaldehyde as specified in ARB's Air Toxics Control Measure for Composite Wood (17 CCR 93120 et seq.), by or before the dates specified in those sections, as shown in Table 4.504.5

4.504.5.1 Documentation. Verification of compliance with this section shall be provided as requested by the enforcing agency. Documentation shall include at least one of the following:

1. Product certifications and specifications.
2. Chain of custody certifications.
3. Product labeled and invoiced as meeting the Composite Wood Products regulation (see CCR, Title 17, Section 93120, et seq.)
4. Exterior grade products marked as meeting the PS-1 or PS-2 standards of the Engineered Wood Association, the Australian AS/NZS 2269, European 636 S3 standards, and Canadian CSA 0121, CSA 0151, CSA 0153 and CSA 0325 standards.
5. Other methods acceptable to the enforcing agency.

4.505 INTERIOR MOISTURE CONTROL

4.505.1 General. Buildings shall meet or exceed the provisions of the *California Building Standards Code*.

4.505.2 CONCRETE SLAB FOUNDATIONS. Concrete slab foundations required to have a vapor retarder by California Building Code, Chapter 19, or concrete slab-on-ground floors required to have a vapor retarder by the California Residential Code, Chapter 5, shall also comply with this section.

4.505.2.1 Capillary break. A capillary break shall be installed in compliance with at least one of the following:

1. A 4-inch (101.6 mm) thick base of 1/2 inch (12.7mm) or larger clean aggregate shall be provided with a vapor barrier in direct contact with concrete and a concrete mix design, which will address bleeding, shrinkage, and curling, shall be used. For additional information, see American Concrete Institute, ACI 302.2R-06
2. Other equivalent methods approved by the enforcing agency.
3. A slab design specified by a licensed design professional.

4.505.3 MOISTURE CONTENT OF BUILDING MATERIALS. Building materials with visible signs of water damage shall not be installed. Wall and floor framing shall not be enclosed when the framing members exceed 19 percent moisture content. Moisture content shall be verified in compliance with the following:

1. Moisture content shall be determined with either a probe-type or contact-type moisture meter. Equivalent moisture verification methods may be approved by the enforcing agency and shall satisfy requirements found in Section 101.8 of this code.
2. Moisture readings shall be taken at a point 2 feet (610 mm) to 4 feet (1219 mm) from the grade stamped end of each piece verified.
3. At least three random moisture readings shall be performed on wall and floor framing with documentation acceptable to the enforcing agency provided at the time of approval to enclose the wall and floor framing.

Insulation products which are visibly wet or have a high moisture content shall be replaced or allowed to dry prior to enclosure in wall or floor cavities. Wet-applied insulation products shall follow the manufacturers' drying recommendations prior to enclosure.

4.506 INDOOR AIR QUALITY AND EXHAUST

4.506.1 Bathroom exhaust fans. Each bathroom shall be mechanically ventilated and shall comply with the following:

1. Fans shall be ENERGY STAR compliant and be ducted to terminate outside the building.
2. Unless functioning as a component of a whole house ventilation system, fans must be controlled by a humidity control.

- a. Humidity controls shall be capable of adjustment between a relative humidity range less than or equal to 50% to a maximum of 80%. A humidity control may utilize manual or automatic means of adjustment.
- b. A humidity control may be a separate component to the exhaust fan and is not required to be integral (i.e., built-in)

Notes:



1. For the purposes of this section, a bathroom is a room which contains a bathtub, shower or tub/shower combination.
2. Lighting integral to bathroom exhaust fans shall comply with the *California Energy Code*.

4.507 ENVIRONMENTAL COMFORT

4.507.2 HEATING AND AIR-CONDITIONING SYSTEM DESIGN. Heating and air conditioning systems shall be sized, designed and have their equipment selected using the following methods:

1. The heat loss and heat gain is established according to ANSI/ACCA 2 Manual J - 2011 (Residential Load Calculation), ASHRAE handbooks or other equivalent design software or methods.
2. Duct systems are sized according to ANSI/ACCA 1 Manual D - 2014 (Residential Duct Systems), ASHRAE handbooks or other equivalent design software or methods.
3. Select heating and cooling equipment according to ANSI/ACCA 3 Manual S - 2014 (Residential Equipment Selection), or other equivalent design software or methods.





Exception: Use of alternate design temperatures necessary to ensure the system functions are acceptable.




ABBREVIATIONS

E or (E) EXISTING TO REMAIN.
N or (N) NEW TO BE ADDED.

LEGEND

	EXISTING WOOD STUD WALL
	WOOD STUD WALL TO BE DEMOLISHED.
	EXISTING WINDOW TO BE REMOVED.
	EXISTING DOOR TO BE REMOVED.



HARDING

DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274
OWNERS: BRIAN AND KERI FOJKS

OWNERS: BRIAN AND KERI FOLKS

project title/type: _____

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title: _____

EXISTING FLOOR PLAN
DEMOLITION PLAN

revisions: _____

R1:

R2:

R3:

R4:

sheet info:

date: 09.29.20

drawn: js

scale: NOTED

reviewed: -

job no: HDC190820

sheet no:

A1.0

Written dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.

GENERAL NOTES


MIN. R-21 EXTERIOR WALL INSULATION.
MIN. R-38 CEILING INSULATION
MIN. R-19 ROOF INSULATION FOR HIGH PERFORMANCE ATTIC.

- THE OWNER/BUILDER SHALL NOTIFY THE DESIGNER IN WRITING IF ANY ERRORS OR OMISSIONS, IN THE EVENT THAT THE OWNER/BUILDER FAILS TO GIVE SUCH NOTICE BEFORE CONSTRUCTION, AND/OR FABRICATION OF THE WORK, THE OWNER/BUILDER WILL BE HELD RESPONSIBLE TO THE RESULT OF ANY ERRORS, DISCREPANCIES OR OMISSIONS AND THE COST OF RECTIFYING THE SAME.
- ON SITE VERIFICATION OF ALL DIMENSIONS AND CONDITIONS SHALL BE THE RESPONSIBILITY OF THE BUILDER.
- ALL INTERIOR WALL FINISHES SHALL BE 1/2" D.W. UNLESS OTHERWISE NOTED.
- ALL NEW WALLS SHALL BE 2"x4" WOOD STUDS, UNLESS OTHERWISE NOTED.
- INTERIOR FINISHES TO BE SELECTED BY INTERIOR DESIGNER & APPROVED BY OWNER.
- STANDARD WOOD FRAME CONSTRUCTION USED THROUGHOUT.
- MAXIMUM SILL HEIGHT AT BEDROOMS 44" ABOVE FINISHED FLOOR.
- ON SITE VERIFICATION OF ALL DIMENSIONS AND CONDITIONS SHALL BE THE RESPONSIBILITY OF THE BUILDER.
- PROVIDE A MINIMUM CLEAR OPENING WIDTH OF 20" & A CLEAR OPENING HEIGHT OF 24" MINIMUM WITH AN OPERABLE AREA OF AT LEAST 5.7 SQ. FT. IF NO EXTERIOR BEDROOM DOOR IS USED.
- THIS PROJECT SHALL COMPLY WITH THE 2019 CEC, CBC, CMC, CPC, CRC, SMMC, 2019 CAL GREEN BUILDING CODE & 2019 TITLE 24 LIGHTING & ENERGY.
- BUILDING MATERIALS WITH VISIBLE SIGNS OF WATER DAMAGE SHALL NOT BE INSTALLED. WALL AND FLOOR FRAMING SHALL NOT BE ENCLOSED WHEN THE FRAMING MEMBERS EXCEED 19 PERCENT MOISTURE CONTENT. INSULATION PRODUCTS THAT ARE VISIBLY WET OR HAVE HIGH MOISTURE CONTENT SHALL BE REPLACED OR ALLOWED TO DRY PRIOR TO ENCLOSURE IN WALL OR FLOOR CAVITIES. (4.505.3)
- ANNULAR SPACES AROUND PIPES, ELECTRICAL CABLES, CONDUITS OR OTHER OPENINGS IN SOLE/BOTTOM PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHODS. (CGB5C 4.406.1)

PLUMBING, ELECTRICAL AND BATHING AREAS

- TOILETS SHALL HAVE AN AVERAGE WATER CONSUMPTION OF NOT MORE THAN 1.28 GALLONS PER FLUSH.
- SHOWER HEADS SHALL HAVE A WATER FLOW NOT TO EXCEED 1.8 GALLONS PER MINUTE AT 80 PSI.
- BATHROOM FAUCETS SHALL HAVE WATER FLOW NOT EXCEED 1.2 GALLONS PER MINUTE.
- SHOWERS AND SHOWER-TUBS SHALL BE PROVIDED WITH INDIVIDUAL CONTROL VALVES OF THE PRESSURE BALANCE, THERMOSTATIC, OR COMBINATION PRESSURE BALANCE/THERMOSTATIC MIXING VALVE TYPE THAT PROVIDE SCALD AND THERMAL SHOCK PROTECTION.
- BATHTUB AND SHOWER FLOORS AND WALLS ABOVE BATHTUBS WITH SHOWERS AND SHOWERS COMPARTMENTS SHALL BE FINISHED WITH A NONABSORBENT SURFACE TO HEIGHT OF 6'-8" ABOVE THE FLOOR (R307.2 CRC).
- CEMENT, FIBER-CEMENT, FIBER-MAT REINFORCED CEMENT, GLASS MAT GYPSUM OR FIBER-REINFORCED GYPSUM BACKERS SHALL BE USED AS A BASE FOR WALL TILE IN TUB AND SHOWER AREAS AND WALL AND CEILING PANELS IN SHOWER AREAS (R702.4.2 CRC).
- ALL PLUMBING FIXTURES AND FITTINGS COMPLY WITH 2019 CGB5C SECTION 4.303.
- LAVATORY FAUCETS SHALL NOT EXCEED 1.2 GALLONS PER MINUTE AT 60 PSI.
- KITCHEN FAUCETS SHALL NOT EXCEED 1.5 GAL PER MINUTE AT 60 PSI.
- OUTLETS IN LIVING ROOM, DINING ROOM, KITCHEN, BEDROOMS, DEN'S, OFFICES, ETC. SHALL BE AFCI AS PER CED 210.12 (A).
- ALL KITCHENS, BATH RM'S, LAUNDRIES, GARAGES & EXTERIOR OUTLETS SHALL BE GFCI.
- ALL EXTERIOR OUTLETS SHALL BE WEATHER PROOF (W. P.).

DOOR & WINDOW SCHEDULE					ENERGY VALUES	
TAG #	SIZE (W/H)	TYPE	QTY.	REMARKS	U-FACTOR	SHGC
DOOR SCHEDULE						
①	5'-0" x 7'-0"	GLASS FRENCH	1			
②	7'-9" x 7'-2"	GLASS SLIDER	1	REPLACE EXSISTING FRENCH DOORS		
③	6'-0" x 7'-0"	GLASS SLIDER	1			
④	2'-8" x 6'-8"	EXTERIOR S.C. DOOR	1	GARAGE EXIT DOOR		
⑤	16'-0" x 7'-0"	SECTIONAL GARAGE DOOR	1			
⑥	2'-8" x 6'-8"	EXTERIOR S.C. DOOR	1			
⑦	2'-8" x 6'-8"	INTERIOR H.C. DOOR	2			
⑧	2'-8" x 6'-8"	POCKET DOOR	2			
⑨	6'-0" x 6'-8"	SLIDERS	1	RE-USE EXISTING CLOSET DOORS		
⑩	2'-6" x 6'-8"	INTERIOR H.C. DOOR	1	RE-USE EXISTING DOOR		
EX	EXISTING DOOR TO REMAIN.					
WINDOW SCHEDULE						
A	4'-0" x 5'-0"	SINGLE HUNG	1	TEMPERED GLASS		
B	2'-0" x 3'-0"	SINGLE HUNG	1			
EX	EXISTING WINDOW TO REMAIN.					



2 FRONT ELEVATION (EAST)
Scale: 1/4" = 1'-0"

ABBREVIATIONS

E or (E) EXISTING TO REMAIN.
N or (N) NEW TO BE ADDED.

LEGEND

EXISTING WOOD STUD WALL
NEW WOOD STUD WALL

- CM CARBON MONOXIDE DETECTOR
HARDWIRED INTERCONNECTED
WITH BATTERY BACK-UP.
- SD SMOKE DETECTOR HARD-WIRED w/
BATTERY BACK-UP (BATTERY OPERATED
@ (E) BEDROOMS). PROVIDE IN AREAS:
- A. IN EACH SLEEPING ROOM.
- B. ENTERALLY LOCATED IN ROOMS &
CORRIDORS GIVING ACCESS TO
SLEEPING AREAS.
- C. SMOKE ALARMS SHALL SOUND AN
ALARM AUDIBLE IN ALL SLEEPING AREAS
OF THE DWELLING UNIT WHICH THEY
SERVE.
- D. PROVIDE BATTERY-OPERATED RETROFIT
DETECTORS.
- MECHANICAL EXHAUST VENT WITH HUMIDITY
CONTROL W/ 50 CFM (BATHROOM EXHAUST
FANS SHALL BE ENERGY STAR COMPLIANT AND
CONTROLLED BY HUMIDISTAT)

- 1 DOOR TYPE, SEE SCHEDULE
- A WINDOW TYPE, SEE SCHEDULE

FLOOR PLAN KEY NOTES

- 1 NEW POST FOR ADDITION. REFER TO
STRUCTURAL FOR CONFIRMATION.
- 2 AREA OF NEW ADDITION.
- 3 STANDARD 1.28 GPF TOILET.
- 4 NEW MASTER BATHROOM WITH VANITY AND
WALK-IN SHOWER.
- 5 NEW POCKET DOOR; VERIFY WALL STRUCTURAL
PRIOR TO INSTALLATION.
- 6 NEW LAUNDRY ROOM.
- 7 NEW MASTER BEDROOM FLOORS TO MATCH
EXISTING.
- 8 NEW WALK-IN STORAGE W/ SINK IN GARAGE.



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274

OWNERS: BRIAN AND KERI FOLKS

project title/type:

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title:

PROPOSED
FLOOR PLAN & ROOF PLAN

revisions:

R1:
R2:
R3:
R4:

sheet info:

date: 09.29.20
drawn: js
scale: NOTED
reviewed: -
job no: HDC190820

sheet no:

A2.0


Written dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.

ELECTRICAL LEGEND


SYMBOL	TYPE
	CEILING FAN
	TYP. LIGHT SWITCH,
	LIGHT SWITCH, 3-WAY
	RECESSED CAN FIXTURE (LED)
	SPOT LIGHT (LED)
	WALL-MOUNTED FIXTURE
	CEILING-MOUNTED FIXTURE
	MOTION SENSOR LIGHT W/ PHOTO CELL SENSOR
	110 DUPLEX OUTLET
	110 DUPLEX OUTLET (1/2 HOT)
	110 QUADRUPLUX OUTLET
	220 OUTLET
	110 GFCI OUTLET
	TELEPHONE
	CABLE/DATA JACK
	TYP. LIGHT SWITCH,
	LIGHT SWITCH, 3-WAY
	LIGHT SWITCH, DIMMER
	TELEVISION
	PENDANT LIGHTING (LED)
	UNDER-CABINET LIGHTING
	OUTLET STRIP
	MOTION DETECTOR
	CARBON MONOXIDE ALARM
	SMOKE DETECTOR
	EXHAUST FAN W/ HUMIDITY CONTROL

ELECTRICAL PLAN NOTES

- ALL SURFACE MOUNTED LIGHT FIXTURES TO BE SUPPLIED BY OWNER, INSTALLED BY CONTRACTOR.
- ELECTRICAL OUTLET LOCATIONS SHOWN ARE FOR CRITICAL LOCATIONS ONLY. ELECTRICAL CONTRACTOR TO PROVIDE ADDITIONAL OUTLETS WHERE REQUIRED BY CODE OR REQUESTED DURING CONSTRUCTION.
- PROVIDE THERMALLY PROTECTED RECESSED FIXTURES WHERE THEY COME IN CONTACT WITH INSULATION.
- PROVIDE 3" AIR SPACE AROUND LIGHT FIXTURES THAT DO NOT HAVE THERMALLY PROTECTED HOUSINGS.
- VERIFY LOCATIONS OF ALL SWITCHES AND OUTLETS WITH OWNER BEFORE WIRING.
- INTERIOR DESIGNER WILL SUPPLY ALL DECORATIVE LIGHT FIXTURES FOR ELEC. TO INSTALL.
- ALL OUTLETS SHALL BE GFCI WITHIN KITCHEN AND BATHROOMS.
- ALL SWITCHES SHALL BE MOUNTED AT 48" A.F.F.
- DIMMER SWITCHES SHALL BE INSTALLED WHERE APPLICABLE.



1 ELECTRICAL PLAN
Scale: 1/4" = 1'-0"



2 ROOF PLAN
Scale: 1/8" = 1'-0"

ABBREVIATIONS


E or (E) EXISTING TO REMAIN.
N or (N) NEW TO BE ADDED.

LEGEND

--- BUILDING LINE
— ROOF LINE
AREA OF NEW ROOF

ROOF PLAN NOTES

- ROOF PLAN IS DIAGRAMMATIC ONLY IT IS THE RESPONSIBILITY OF ENGINEER TO DETERMINE THE FEASIBILITY OF LAYOUT & TO PROVIDE ACCURATE & EXACT CALCULATIONS.
- AT THE TIME OF ROUGH INSTALLATION, OR DURING STORAGE ON THE CONSTRUCTION SITE AND UNTIL FINAL START UP OF THE HEATING, COOLING AND VENTILATING EQUIPMENT, ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEET METAL OR OTHER ACCEPTABLE METHODS TO REDUCE THE AMOUNT OF WATER, DUST AND DEBRIS THAT MAY ENTER THE SYSTEM. (4.504.1)
- PROVIDE UNOBSTRUCTED 24" WIDE PLYWOOD FLOOR PASSAGEWAY FROM ATTIC ACCESS TO F.A.U. AND SHALL NOT EXCEED 20 FT. MAX. LENGTH. PROVIDE ELECTRIC AND FUEL GAS AS REQUIRED BY UNIT. INSTALLED FURNACE SHALL MEET ALL CLEARANCES TO COMBUSTIBLES.



3 FRONT ELEVATION (EAST)
Scale: 1/4" = 1'-0"



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274

OWNERS: BRIAN AND KERI FOLKS

project title/type:

FOLKS RESIDENCE

ADDITION/REMODEL

sheet title:

FRONT ELEVATION &
ROOF PLAN

revisions:

R1:

R2:

R3:

R4:

sheet info:

date: 09.29.20

drawn: js

scale: NOTED


reviewed: -

job no: HDC190820

sheet no:

A3.0

Within dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.



HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz

27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274

OWNERS: BRIAN AND KERI FOLKS

project title/type:

FOLKS RESIDENCE
ADDITION/REMODEL

sheet title:

PROPOSED
EXTERIOR ELEVATIONS

revisions:

R1:
R2:
R3:
R4:




sheet info:


date: 09.29.20
drawn: js
scale: NOTED
reviewed: -
job no: HDC190820

sheet no:

A4.0

Written dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.






HARDING
DESIGN & CONSTRUCTION

562.333.6392
info@hardingconstruction.biz


27361 RAINBOW RIDGE
PALOS VERDES PENINSULA, CA 90274

OWNERS: BRIAN AND KERI FOLKS



NOTE:
1. REFER TO STRUCTURAL FOR ALL ASSEMBLY AND DETAILS
2. MATCH EXISTING TOP PLATE THROUGHOUT.
3. CONTRACTOR TO VERIFY ALL DIMENSIONS AND CONDITIONS AT THE JOB SITE PRIOR TO BEGINNING WORK AND SHALL REPORT ANY DISCREPANCIES TO THE ENGINEER.

CROSS SECTION B
Scale: 1/4" = 1'-0"



NOTE:
1. REFER TO STRUCTURAL FOR ALL ASSEMBLY AND DETAILS
2. MATCH EXISTING TOP PLATE THROUGHOUT.
3. CONTRACTOR TO VERIFY ALL DIMENSIONS AND CONDITIONS AT THE JOB SITE PRIOR TO BEGINNING WORK AND SHALL REPORT ANY DISCREPANCIES TO THE ENGINEER.

SECTION A
Scale: 1/4" = 1'-0"

project title/type:

FOLKS RESIDENCE
ADDITION/REMODEL

sheet title:

BUILDING SECTIONS

revisions:

R1:
R2:
R3:
R4:

sheet info:

date: 09.29.20
drawn: js
scale: NOTED
reviewed: -
job no: HDC190820

sheet no:

A5.0

Written dimensions on these drawings shall have precedence over scaled dimensions. Drawings shall not be scaled. Contractors shall verify, and be responsible for, all dimensions and conditions shown by these drawings. Shop details must be submitted to this office for approval before proceeding with fabrications.