AJ Pools
2472 Kennedy Ave
Chico, CA 95973

CA Lic # 950638

Estimate

Date	Job #
10/28/26	26/53

Estimate Submitted to:		Job Name:
Nicole Wright	Contact Person:	1454 Lazy Trail Dr Chico, CA 95926
	Nicole	
	Phone	

We hereby submit specifications and estimate for:

Plaster Pool, 160 Perimeter Feet, 3.5' to 8' Deep
Color:Medium Tahoe
~~~
Preparation:
Wet Blast to Remove Loose Plaster
Apply Bond Coat
~~~
Replaster Pool:
Install ASME/ ANSI A112.19.8a-2008 Compliant Main Drain Covers
Obtaining a Smooth Medium Tahoe Plaster finish, 1/2" overall Thickness
~~~
Note:
Time necessary to complete the above work approximately 15 working days, weather permitting.

**ALTERNATES MAY REQUIRE ADDITIONAL WORK DAYS**

WE PROPOSE HEREBY TO FURNISH MATERIAL AND LABOR-COMPLETE IN ACCORDANCE WITH ABOVE SPECIFICATIONS, FOR THE SUM OF: ***$16,650.00***

Payment to be made as follows: PAYMENT FOR ABOVE ALTERNATES TO BE INCLUDED IN PROGRESS BILLING:

**10% Deposit, 60% Due After Preparation, 30% Due After Plastering**

| Terms | 100% Due on receipt | *Past Due 10 Days From Billing Date* |
|---|---|---|

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary Insurance.

NOTE: This estimate may be withdrawn by us if not accepted within 30 days.

Signature: _____ Date: 10/28/26

ACCEPTANCE OF ESTIMATE- The above prices, terms, progress billing, specifications and conditions are satisfactory. Please contact our office for a complete contract to authorize the above work as specified.
~~~