

Paradise Pool and Spa, Inc.

2785 Pacific Coast Hwy, #E809
Torrance, CA 90505
(310) 370-2144



Quote

ADDRESS	SHIP TO	QUOTE	1776
Freddy Carbajal	Freddy Carbajal	DATE	09/27/2023
3111 Deluna Drive	3111 Deluna Drive		
Rancho Palos Verdes	Rancho Palos Verdes		
California 90505	California 90505		

DESCRIPTION	AMOUNT
Draft plans and draw permits with the city. Meet with inspectors as needed.	2,500.00
Drain the pool. Chip out the plaster down to the gunite. Haul away and dispose of the old material. Prepare the surface and install three layers of white marble plaster.	9,805.00
Remove and replace the waterline tile with swimming pool grade tile up to price group four tile. \$10/sf allowance.	3,776.00
Upgrade the light to meet current code and eliminate the junction box. Open the deck and install a new conduit. Install a new junction box and white LED light fixture. Install a new GFCI and switch if needed. The switch may not be located in its original place when complete.	3,800.00
To meet State/Federal anti-entrapment code (California Health and Safety Code 115928) install a 3 foot channel suction cover. No charge, we want safe pools.	0.00
Provide the startup service to cure the new plaster and treat the new water once complete. We are certified by the National Plaster Council to conduct startup services. We incorporate the Orenda startup for longer lasting plaster. https://www.youtube.com/watch?v=E_J436kmosU	1,100.00
Crack Repair: Open the wall of the pool expose the cracks. Remove the excess/failed material. Stitch the wall with rebar and re-pack concrete. Patch the wall when complete. The patch will not be an exact match. Includes up to 15' of cracks. More than 15' is \$100 per linear foot. - Note: More extensive structural repair may be needed. We will know better when the plaster is stripped from the walls.	4,500.00
Re-plumb the pool. Install a new skimmer caged in rebar and concrete. Install a new suction line, two new return lines and split suction points on the wall. Install a dedicated cleaner port. Backfill trenches and patch the area removed.	8,500.00
Remove and replace the pump and filter. - Hayward TriStar variable speed pump with GFCI - Hayward 425sf cartridge filter.	4,850.00
Additional Option: Install a two jet swim jet system in the deep end wall. \$11,500 Note: Additional work may be needed to run new electrical for a swim jet pump. We would have a tech check it out prior to starting the work.	
TOTAL	\$38,831.00