

Kurt Norlander Roofing

PO Box 858
Lake Arrowhead, CA 92352 US
knroofing1@hotmail.com

Estimate

ADDRESS
Fremont 106
106 Fremont Dr
Lake Arrowhead, CA

ESTIMATE 1525
DATE 06/28/2023
EXPIRATION DATE 08/31/2023

DATE	SERVICE	DESCRIPTION	QTY	RATE	AMOUNT
	Sales	Complete roof replacement of home, removal and disposal of existing wood shake roofing, inspect all plywood and fascias, install new felt (titanium underlayment) with ice barrier along all eaves, install new edge metal flashing and vent flashings, install GAF timberline or Certainteed Landmark shingles (installed to manufacturers specs with 5-6 nails per shingle) with high definition ridge caps.			13,500.00
	Sales	County Roof Permit			380.00

Wood repairs or plywood installation not included, if plywood repairs are required \$180 per sheet to replace or \$8 per ft for 1x8 sheathing, \$15 per ft 2x6 Sheathing.

TOTAL

\$13,880.00

Accepted By

Accepted Date