

PROPOSED FLOOR PLAN

SCALE: 3/16"= 1'-0"

NOTES:

1. The Sprinkler System shall be approved by Plumbing Division prior to installation.
2. Enclosed accessible space under stairs shall have walls, under stair surface and any soffits protected on theenclosed side with 1/2 inch gypsum board.
3. Plans shall state that the fireplace is direct-vent, sealed combustion type, gas log, or pellet stove or pellet stove shall comply with U.S. EPA New Source Performance Standards (NSPS) emission limits as applicable to the fireplace pellet stove being installed. Any wet stove or outdoor hydronic heater shall be certified to meet the emission limits, in accordance manufacturers specifications onto stove. (A609.1)
4. Wood burning fireplaces and other wood burning devices are prohibited.

LEGEND:

EXISTING WALL TO REMAIN

EXISTING WALL TO BE REMOVED

NEW 2x4 STUDS @ 24" O.C. W/ 5/8" GYPSUM BOARD EACH SIDE INTERIOR WALLSNEW 2x6 STUD @ 16IN OF EXTERIOR WALLS W/ 5/8" GYPSUM BOARD ON INTERIOR SIDE OF WALLS W/ R-19 MIN. INSULATION EXTERIOR WALL W/ STUCCO FINISH

EXHAUST FAN W/ 80 cfm EXHAUSTED DIRECTLY TO OUTSIDE (FOR BATHROOMS ONLY) (DAMP STAT AND HUMIDITY AT CONTROL)

HARD WIRED SMOKE ALARMS WITH BATTERY BACKUP IS

HARD WIRED INTERCONNECTED CARBON MONOXIDE

2" MAX DROP