

OTTO B PLUMBING

15525 Jumper Mine Rd
Jamestown, CA 95327-9125 USA
(209) 559-8890
ottobplumbing@gmail.com

Estimate

ADDRESS
Aniko Vera

ESTIMATE 1141
DATE 08/07/2026

DATE	SERVICE	DESCRIPTION	QTY	RATE	AMOUNT
	23808 Leisure Dr		1	0.00	0.00
	Warranty	Workmanship is warranted for one (1) year from the date of completion. Manufacturer warranties apply to materials where applicable.	1	0.00	0.00
	Scope of Work	'Remove existing septic tank lids/access components as required 'Furnish and install new septic tank risers up to 24" (2 feet) in height, bringing access points closer to furnished grade for easier future inspection, maintenance, and pumping. 'Install new secure riser lids and properly seal risers to the septic tank to help prevent groundwater, dirt, and debris from entering tank. 'Excavate and expose the existing tank inlet line. 'Remove the damaged or deteriorated portion of the inlet piping and inlet downspout/baffle. 'Furnish and install new approved piping and fittings from the existing inlet sewer line into the septic tank. Verify proper pitch, alignment, and flow into the septic tank. Backfill excavated areas after completion of work and rough grade disturbed soil.	1	0.00	0.00
	Exclusions	Landscaping restoration, concrete/asphalt replacement, engineering, permits, and repairs to unforeseen damaged components are not included unless specifically stated in the estimate. Any additional repairs discovered after excavation will be discussed with the customer before additional work is performed	1	0.00	0.00
	Services		1	1,500.00	1,500.00

Check

SUBTOTAL

1,500.00

TAX	0.00
-----	------

TOTAL	\$1,500.00
-------	-------------------

Accepted By

Accepted Date